



LABOR RELATIONS DIVISION

401 Broadway NE
 Albuquerque, NM 87102
 Phone: 505-841-4400
 Fax: 505-841-4424

226 South Alameda Blvd
 Las Cruces, NM 88005
 Phone: 575-524-6195
 Fax: 575-524-6194

WWW.DWS.STATE.NM.US

1596 Pacheco St, Suite 103
 Santa Fe, NM 87505
 Phone: 505-827-6817
 Fax: 505-827-9676

Wage Decision Approval Summary

1) Project Title: Outdoor Learning Shade Structures
 Requested Date: 01/20/2022
 Approved Date: 01/21/2022
 Approved Wage Decision Number: SJ-22-0152-A

Wage Decision Expiration Date for Bids: 05/21/2022

2) Physical Location of Jobsite for Project:
 Job Site Address: 550 RD 6100
 Job Site City: Kirtland
 Job Site County: San Juan

3) Contracting Agency Name (Department or Bureau): Central Consolidated School District
 Contracting Agency Contact's Name: Waynette Danley
 Contracting Agency Contact's Phone: (505) 598-4561 Ext.

4) Estimated Contract Award Date: 12/17/2022

5) Estimated total project cost: \$523,552.00
 a. Are any federal funds involved?: No
 b. Does this project involve a building?: No
 c. Is this part of a larger plan for construction on or appurtenant to the property that is subject to this project?: No
 d. Are there any other Public Works Wage Decisions related to this project?: No
 e. What is the ultimate purpose or functional use of the construction once it is completed?: Install two each 30x40 metal shade structures with metal column supports on concrete pads. Install five each 12x12 metal shade structures with metal column supports. Five each cantilever structure, 8' deep x 8' wide.

6) Classifications of Construction:

Classification Type and Cost Total	Description
Highway/Utilities (A) Cost: \$523,552.00	Install two each 30x40 metal structure with 6 columns and 2 hips at the end of the roof line. Structure is 8' clear to the eve. All metal will be powder coated to match school colors. Roof will be standard 26 gauge R panel galvalume. Concrete footings. 4" concrete pad under the canopy. Install five each 12x12 metal structure with 4 columns and 4 hips in the roof canopy. Structure is 8' clear to the eve. All metal will be powder coated to match school colors. Roof will be standard 26 ga galvalume. Concrete footings. Five each cantilever structure, 8' deep x 8' wide with 2. The low side is 8' clear to the eve. All metal will be powder coated to match school colors. Roof will be standard 26 ga R panel galvalume