



**LABOR RELATIONS DIVISION**

401 Broadway NE  
 Albuquerque, NM 87102  
 Phone: 505-841-4400  
 Fax: 505-841-4424

226 South Alameda Blvd  
 Las Cruces, NM 88005  
 Phone: 575-524-6195  
 Fax: 575-524-6194

**WWW.DWS.STATE.NM.US**

1596 Pacheco St, Suite 103  
 Santa Fe, NM 87505  
 Phone: 505-827-6817  
 Fax: 505-827-9676

**Wage Decision Approval Summary**

1) Project Title: Central Office Parking Lot Replacement...ED...Sunland...222308  
 Requested Date: 06/06/2022  
 Approved Date: 06/07/2022  
 Approved Wage Decision Number: MC-22-1512-A

**Wage Decision Expiration Date for Bids: 10/05/2022**

2) Physical Location of Jobsite for Project:  
 Job Site Address: 10 N Sandy Springs Road  
 Job Site City: Zuni  
 Job Site County: McKinley

3) Contracting Agency Name (Department or Bureau): Zuni Public Schools  
 Contracting Agency Contact's Name: Martin Romine  
 Contracting Agency Contact's Phone: (505) 782-5511 Ext. 6301

4) Estimated Contract Award Date: 05/24/2022

5) Estimated total project cost: \$899,618.04  
 a. Are any federal funds involved?: No  
 b. Does this project involve a building?: No  
 c. Is this part of a larger plan for construction on or appurtenant to the property that is subject to this project?: No  
 d. Are there any other Public Works Wage Decisions related to this project?: No  
 e. What is the ultimate purpose or functional use of the construction once it is completed?: Repave Central Office parking lot and replace concrete

6) Classifications of Construction:

Classification Type and Cost Total	Description
<b>Highway/Utilities (A)</b> <b>Cost: \$899,618.04</b>	Repave parking lot and replace concrete. ADA Parking North Area-Flush Pan Ramp Approximately 26 X 7 Parking Pad Approximately 29 X 20 X 6". ADA Parking South Area-parking Pad Approximately SO X 30 X 6" Stockpile And Reset Brick Pavers Approximately 30 Lf. Sidewalk Panels North Area - Remove And Replace - Tree Roots .Approximately SOX 12 X 4". Sidewalk Panels South Area Adjacent To ADA Parking Pad- Approximately 30 X 30 X 6". Valley Gutter North Area-Approximately 164 X 4 X 8". Valley Gutter South Area -Approximately 208 X 4 X 8" Loading Dock Pad-Approximately 90 X 25 X 8". Estate Curb - Approximately 85 X 2 X 6", Curb & Gutter. Provide Traffic Control And Barricades During Our Scope Of Work. Make Necessary Sawcuts. Remove Approx. 72,393 Square Feet Of Asphalt To A Depth Of 3 Inches. Move Cuts To Fills. Excavate Approx. 72,393 Square Feet To A Depth Of 6 Inches. Export 1,340 Cubic Yards Of Soil To An Off-

site Dump. Fine Grade, Moisture Condition, And Compact Subgrade To +/- 0.10 Of A Foot On Approx. 72,393 Square Feet. Construct A 6 Inches Aggregate Base Course (ABC) Section On Approx. 72,393 Square Feet. Fine Grade Aggregate Base Course, Add Moisture, And Compact To Grade On Approx. 72,393 Square Feet. Pave Approx. 72,393 Square Feet With SP-IV Asphalt To An Average Finished Depth Of 3 Inches After Compaction With A Steel Wheeled Vibratory Roller. This Proposal Is Based On Performing The Work In 1 Sections Over 34 Continuous Working Days. Stripe Regular 90 Degree Spaces White. Stripe ADA Spaces. Reset Parking Blocks. Replacing Parking Blocks. Paint Parking Blocks Blue. Paint Parking Blocks Yellow. Demo Old U Channel Post Signs In South ADA Area. Install Wall Mount ADA Signs. Install Wall Mount Van Accessible Signs.