



**LABOR RELATIONS DIVISION**

401 Broadway NE  
 Albuquerque, NM 87102  
 Phone: 505-841-4400  
 Fax: 505-841-4424

226 South Alameda Blvd  
 Las Cruces, NM 88005  
 Phone: 575-524-6195  
 Fax: 575-524-6194

**WWW.DWS.STATE.NM.US**

**Wage Decision Approval Summary**

1) Project Title: MDC Guard Shack  
 Requested Date: 06/13/2024  
 Approved Date: 06/14/2024  
 Approved Wage Decision Number: BE-24-2068-B

**Wage Decision Expiration Date: 10/12/2024**

2) Physical Location of Jobsite for Project:  
 Job Site Address: 100 Deputy Dean Miera Dr. SW  
 Job Site City: Albuquerque  
 Job Site County: Bernalillo

3) Contracting Agency Name (Department or Bureau): Bernalillo County  
 Contracting Agency Contact's Name: David Conkle  
 Contracting Agency Contact's Phone: (505) 364-3481 Ext.

4) Estimated Contract Award Date: 07/13/2022

5) Estimated total project cost: \$91,000.00  
 a. Are any federal funds involved?: No  
 b. Does this project involve a building?: Yes - Electrical for the guard shack  
 c. Is this part of a larger plan for construction on or appurtenant to the property that is subject to this project?: No  
 d. Are there any other Public Works Wage Decisions related to this project?: No  
 e. What is the ultimate purpose or functional use of the construction once it is completed?: Fully functional guard shack

6) Classifications of Construction:

<b>Classification Type and Cost Total</b>	<b>Description</b>
<b>General Building (B)</b> <b>Cost: \$91,000.00</b>	Electrical to supply power for the new checkpoint area access gate and permanent guard shack. Install 200 ft of 2in EMT in mechanical chasses. Core drill (3) 2in holes 1 penetrating the exterior building, one for the 1st floor and 2nd floors levels. Dig (2) boar pits. Boar 851ft for 2in conduit. Install (1) 45KVA transformer with weather guards. Install (1) 42 space NEMA 3R Panelboard. Supply power to existing guard shack at new location. Supply power to new access gate. Supply power for (1) flood light (location TBD by MDC personal). Pull new 1/0 conductors from E POD to new guard shack location. Install (1) 60 AMP 277/480 3PH breaker (utilize 277/480 existing panel). Test voltage at transformer and new panel.