



LABOR RELATIONS DIVISION

401 Broadway NE
 Albuquerque, NM 87102
 Phone: 505-841-4400
 Fax: 505-841-4424

226 South Alameda Blvd
 Las Cruces, NM 88005
 Phone: 575-524-6195
 Fax: 575-524-6194

WWW.DWS.STATE.NM.US

1596 Pacheco St, Suite 103
 Santa Fe, NM 87505
 Phone: 505-827-6817
 Fax: 505-827-9676

Wage Decision Approval Summary

1) Project Title: Football Field and Track Renovation CES KES
 Requested Date: 02/01/2023
 Approved Date: 02/02/2023
 Approved Wage Decision Number: ED-23-0314-A

Wage Decision Expiration Date for Bids: 06/02/2023

2) Physical Location of Jobsite for Project:
 Job Site Address: 602 S 6th St
 Job Site City: Loving
 Job Site County: Eddy

3) Contracting Agency Name (Department or Bureau): Loving Municipal Schools
 Contracting Agency Contact's Name: Oralía Galindo
 Contracting Agency Contact's Phone: (575) 745-2007 Ext.

4) Estimated Contract Award Date: 02/01/2023

5) Estimated total project cost: \$1,900,000.00
 a. Are any federal funds involved?: No
 b. Does this project involve a building?: No
 c. Is this part of a larger plan for construction on or appurtenant to the property that is subject to this project?: No
 d. Are there any other Public Works Wage Decisions related to this project?: No
 e. What is the ultimate purpose or functional use of the construction once it is completed?: To have a nice track and field for their sports and PE.

6) Classifications of Construction:

Classification Type and Cost Total	Description
Highway/Utilities (A) Cost: \$1,900,000.00	Football Filed 1. Protect running track and other existing finishes. 2. Excavate and dispose of approximately 7" of soil. Compact subgrade to 95% 3. Furnish and install new 8" in-ground perforated collector pipes for field drainage. Bore under track and daylight collector system into concrete channel on southwest corner. Cut and repair concrete. 4. Furnish and install Marafi 140N filter fabric over entire subgrade. 5. Furnish and install 6" of crushed aggregate: 4" of coarse rock and 2" of finish rock. Laser grade to +/- 1/4" in 10 feet. 6. Furnish and install 2-1/4" GeoSurfaces 50-ounce fiber weight slit-film synthetic turf by Tencate for football with inlaid gridiron including yard lines, tics, hash marks, numbers and arrows. Layout, colors, inlays, fonts, and logos as shown on attached drawings. 7. 8-year manufacturer's turf warranty. 8. Prevailing wage and 100% payment and performance bonds. 9. Clean-up and incidentals for complete work.

	<p>Running Track</p> <ol style="list-style-type: none"> 1. Demo and dispose of existing running track surface on oval, high jump, and runways. 2. Repair asphalt deficiencies that can be seen prior to demo such as soft spot in first lane on southeast corner, and cracks on northeast straightaway. Excludes repairs or replacement of asphalt due to conditions not apparent by visual inspection. 3. Repair long-jump/triple jump and pole vault runways, replace take-off boards where broken. Clean sand pits, furnish new sand, furnish new ballasted woven polyester sand pit covers. 4. Furnish and install permeable 13mm two-layer Stockmeier SC polyurethane base mat with red structural spray running track system on 400m oval, high jump, and long jump/triple jump and pole vault runways. 5. Option for impermeable 13mm three-layer Stockmeier SW red polyurethane sandwich track system. 6. Paint lane lines and event markings to NFHS and NMAA standards. 7. Prevailing wage and 100% payment and performance bonds. 8. Clean-up and incidentals for complete work.
--	---