



LABOR RELATIONS DIVISION

401 Broadway NE
Albuquerque, NM 87102
Phone: 505-841-4400
Fax: 505-841-4424

226 South Alameda Blvd
Las Cruces, NM 88005
Phone: 575-524-6195
Fax: 575-524-6194

WWW.DWS.STATE.NM.US

1596 Pacheco St, Suite 103
Santa Fe, NM 87505
Phone: 505-827-6817
Fax: 505-827-9676

Wage Decision Approval Summary

1) Project Title: Main Street District Waterlines
Requested Date: 03/17/2022
Approved Date: 03/21/2022
Approved Wage Decision Number: SI-22-0735-A/H

Wage Decision Expiration Date for Bids: 07/19/2022

2) Physical Location of Jobsite for Project:
Job Site Address: Downtown/Main Street District
Job Site City: Truth or Consequences
Job Site County: Sierra

3) Contracting Agency Name (Department or Bureau): City of Truth or Consequences
Contracting Agency Contact's Name: Carol Kirkpatrick
Contracting Agency Contact's Phone: (575) 740-7323 Ext.

4) Estimated Bid Opening Date: 11/18/2021

5) Estimated total project cost: \$8,000,000.00
a. Are any federal funds involved?: Yes - \$8,000,000.00
b. Does this project involve a building?: No
c. Is this part of a larger plan for construction on or appurtenant to the property that is subject to this project?: No
d. Are there any other Public Works Wage Decisions related to this project?: No
e. What is the ultimate purpose or functional use of the construction once it is completed?: Potable Water System

6) Classifications of Construction:

Classification Type and Cost Total	Description
Highway/Utilities (A) Cost: \$5,000,000.00	Project is to replace 23,600-feet of waterline in the Main Street District (MSD) of the City of Truth or Consequences with 6, 8, and 12-inch PVC waterline via open trench, pipe bursting, and horizontal directional drilling. All service connection will be replaced with new service lines, meter cans, and meters.
Heavy Engineering (H) Cost: \$3,000,000.00	Upgrades to the Cook Street Booster Station site to include gas chlorination system, VFD booster pumps with electrical, diesel generator, meter and chlorination injection vaults, SCADA system, and a 300,000 - gallon steel ground water storage tank.